

MICRO-COMBINED HEAT AND POWER: BRIDGE TO YOUR ENERGY FUTURE

Tony Ranallo
Principal
BOILERSOURCE

Why Are We Here Today?



Energy Efficiency
PROGRAM

- **Identify the Issues**
- Review the Technologies
- Meet the Manufacturers and Products
- Target Markets and Applications
- Making It Easy

Industry Overview




Energy Efficiency
PROGRAM

The Problem: Homes and Businesses Need Resilient and Affordable Clean Power

America's Grid is Unreliable



Power Costs are Increasing



We Need Cleaner Power




mCHP Products

- Award winning
- Green
- Affordable
- Practical
- Tested and validated
- Patent Cooperation Treaty ("PCT") patented
- Multi fuel mix, including hydrogen

Select Product Overview


Combined Heat and Power ("CHP") Offers High Efficiency, Energy Security, and Significant Decarbonization



CHP systems have been successfully used for decades in the industrial sector and are twice as efficient as the most efficient conventional gas power plants. mCHP systems are a miniaturized and optimized version of these industrial-scale systems.

The US is Heading into an Energy Crisis

NERC: LONG-TERM RELIABILITY ASSESSMENT



“By the summer of 2026 we will have supply disruption”

-Executive Director PJM

“By the summer of 2027 we will see voltage collapse”

-Executive Director PJM

Newest assessment even darker...

"By the summer of 2026 we
will have **supply disruption**"

-Executive Director PJM

"By the summer of 2027 we
will see **voltage collapse**"

-Executive Director PJM




Figure 1: Risk Area Summary 2026–2030

Shows highest risk classification that occurs in the first 5 years and states initial year of occurrence


Why Are We Here Today?



Energy Efficiency
PROGRAM


- Identify the Issues
- **Review the Technologies**
- Meet the Manufacturers and Products
- Target Markets and Applications
- Making it Easy

mCHP – Innovative Technology




mCHP 90+ % efficiency v. 30-40% efficiency with conventional power grid

Conventional Power Plant



mCHP




Energy Center Main Advantages



Energy Efficiency
PROGRAM

- Flexibility of components and fuel
 - Natural Gas, Propane, Biogas (only EU), H2 Ready
- Lower dependency on any one fuel (oil, gas, electricity)
- Partially independent from grid – resistant to blackouts
- Significantly lower CO² emissions
- Low operating costs – short payback time
- Turn energy use from a cost center to a profit center
- Higher efficiency
- Mature, reliable product
- **It simply works!**



Regarded as Superior Technology



Energy Efficiency
PROGRAM

Combined Heat and Power is regarded by the Environmental Protection Agency (EPA), Department of Energy (DOE) and the Energy Information Agency (EIA) as one of the most affordable, cleanest, efficient and reliable energy sources available.

[EPA - CHP is Superior for Hospitals](#)

[EPA - CHP offers Efficiency, Environmental, Economical and Reliability Benefits](#)

[DOE - CHP can Improve Nation's Energy, Economic, Environmental Future](#)

[DOE - CHP can be Deployed Quickly, Cost-Effectively, and With Few Geographic Limitations](#)

[EIA - CHP Fills an Important Energy Niche](#)

[EIA - CHP is one of the Most Efficient and Effective Sources of Electric Generation](#)

Why Are We Here Today?



Energy Efficiency
PROGRAM


- Identify the Issues
- Review the Technologies
- **Meet the Manufacturers and Products**
- Target Markets and Applications
- Making it Easy

Axiom Energy mCHP System Overview




Energy Efficiency
PROGRAM

Compact and Modular



- 1.2 - 4.4 kWh of electricity (single phase)
- 15,000 - 47,000 btu/hr of heat - Propane
- 13,000 - 42,500 btu/hr of heat - NG
- Exhaust Gas Temperature 1800° F
- Overall efficiency = 93%
- Sound Level - 55dB



Chicago Multifamily mCHP

Success Story: 5550 S. Dorchester Avenue, Chicago, IL



"Imagine if your water heater also made electricity and you didn't have to spend any more to keep it running."

— Jon Nichols,
Director of Sustainability for Antheus Capital/
Fernwood Property Management

Installed equipment

- Two Axiom Energy 4.4 kW mCHP units
- Integration with existing domestic hot water infrastructure
- On-site electricity generation for common-area building loads

Projected energy impact

- 50,000 kWh generated annually
- 20% of building electric load offset
- Recovered waste heat met 55% of annual hot water demand
- 95% total fuel utilization efficiency through mCHP generation

Building benefits

- Lower operating costs
- Improved energy efficiency
- Reduced strain on existing equipment
- Project completed in less than six months

How a Chicago apartment building improved efficiency and generated its own power with a micro combined heat and power (mCHP) system

The Peoples Gas Energy Efficiency Program helps multifamily building owners identify innovative ways to reduce energy costs while improving building performance.

At 5550 S. Dorchester in Chicago's Hyde Park neighborhood, a mCHP system was installed to generate electricity on-site while providing useful thermal energy for domestic hot water production.

The project demonstrates how mCHP technology can be successfully integrated into a typical multifamily building to improve efficiency, reduce operating costs, and increase overall system performance.

Key takeaways

Two 4.4-kilowatt (kW) Axiom Energy mCHP units were installed at a 120-unit multifamily residential building managed by Fernwood Property Management and Antheus Capital.

The system generates electricity that is used to offset common-area electrical demand within the building while simultaneously recovering thermal energy that is used to preheat domestic hot water.

The project was completed in less than six months and demonstrates how mCHP technology fits successfully in a typical multifamily building to drive energy savings and lower operating costs.



Energy Efficiency
PROGRAM

Addressing multifamily energy challenges

Like many multifamily buildings, 5550 S. Dorchester relies on centralized systems to provide domestic hot water and heating to residents.

Prior to the project, the building's domestic hot water system was operating reliably but required significant energy to meet demand. At the same time, rising electricity costs were increasing pressure on operating budgets.

The property owner was interested in identifying technologies capable of reducing energy costs while maintaining resident comfort and reliable service.

"5550 S. Dorchester is a regular old multifamily building," explained Jon Nichols, Director of Sustainability for Antheus Capital and Fernwood Property Management. "It's pretty typical of our portfolio."

The project offered an opportunity to evaluate whether mCHP technology could provide value not only for this property but potentially for other buildings throughout the company's portfolio.

Optimizing energy use with mCHP

Working with the Peoples Gas Energy Efficiency Program and project partners Boilersource and Premistar, the building owner evaluated opportunities to integrate mCHP technology into the existing domestic hot water system.

Because the technology was integrated into existing infrastructure, installation was completed with minimal disruption to residents and building operations.

The system's initial results are:

- Generate approximately **50,000 kWh** annually
- Supply approximately **55%** of domestic hot water demand
- Offset approximately **20%** of the building's electric load


"The installation of the mCHP has taken out a real chunk of our electricity cost," said Nichols. "Being able to reduce that kW demand is enormous."

The project also demonstrates that mCHP technology can be successfully deployed in typical multifamily buildings rather than only large commercial or industrial facilities. mCHP is a decarbonization opportunity for property owners looking to reduce their building's carbon footprint while meeting their energy needs.

"Almost any of our legacy buildings could be appropriate," Nichols noted.

For property owners facing rising energy costs, that may be the most valuable takeaway of all.





 BOILERSOURCE Going Beyond the Boileplate	19 WEST COLLEGE DRIVE ARLINGTON HEIGHTS, IL 60004 (847) 253-1040 BOILERSOURCE.COM	DRAWN BY AGR	PROJECT 5550 S DORCHESTER, CHICAGO, IL.	REVISION 4
		CHECKED BY	DRAWING TITLE	DATE 1/8/26
		SCALE NONE	TWO AXIOM ECOPRIME mCHP WITH BUFFER TANK FOR DHW ONLY	SHEET



Energy Efficiency
PROGRAM



* Storage tank is not included
in the basic price


STORAGE TANK

- Stores excess heat in the event of high demand for electricity
- Reserve in the event of high demand for heat



POWER UNIT

- Engine drives generator
- Generator produces electricity
- Heat exchanger transfers heat to the Q-Heat Distributor



Q-HEAT DISTRIBUTOR

- Absorbs heat from the Power Unit
- Distributes heat to the water circuit and/or Storage Tank.

IQ-CONTROL PANEL

- Controls the system to meet requirements
- Analyses in real-time your consumption patterns and optimises operation fully automatically

- 12 - 24 kWh of electricity (480/3/60)
- 112,000 - 163,000 BTUH of heat - NG
- Water supply temperature ~185° F
- Total overall efficiency = 93%
- 49dB

Half Acre Beer Company mCHP Project

Success Story



Energy Efficiency
PROGRAM



"We've done a lot of work in the sustainability area already. The engineering study showed this was the biggest opportunity we still had."

— Travis Hixon,
Director of Operations for
Half Acre Beer Company

Installed equipment

- Two EC Power XRGI-25 mCHP units
- Two 450-gallon storage tanks
- Integrated heat recovery and hot water preheating system

Projected energy impact

- Generate up to 48 kilowatts (kW) of on-site electricity
- 14% of building electric load offset
- Recovered waste heat met 59% of annual hot water demand
- 93% total fuel utilization efficiency through mCHP generation

Projected annual impact

- \$17,888 net operating savings
- 138,000 kilowatt hours (kWh) electricity savings

A better batch of savings: how Half Acre Beer Company puts every therm to work

The Peoples Gas Energy Efficiency Program helps businesses identify innovative ways to reduce operating costs by improving energy efficiency.

When Half Acre Beer Company wanted to understand where it could make its next meaningful energy improvement, an engineering study pointed to an opportunity hiding in plain sight. By installing a micro combined heat and power (mCHP) system, the brewery now uses natural gas to generate electricity on-site while putting recovered heat to work in the brewing process — helping lower overall energy costs without disrupting production.

Looking beyond the obvious

After years of investing in sustainability and efficiency, Half Acre has already completed many of the improvements typically recommended for breweries. Rather than assuming there was little left to gain, the brewery applied for an engineering study from the Peoples Gas Energy Efficiency Program to take a closer look at mCHP.

The engineering study confirmed mCHP could successfully improve overall energy performance. Even better, rising electricity prices made generating power on-site with natural gas even more valuable than originally projected.

"We've done a lot of work in the sustainability area already," said Travis Hixon, Director of Operations. "This was the biggest opportunity we still had."

Making a complex project feel simple

Implementing the technology was new to a brewery of Half Acre's size.

Working with the Peoples Gas Energy Efficiency Program and project partners Kinergetics, Boilersource, and Stanton Mechanical, the brewery found a way to integrate the system into its existing facility despite limited available space. Installation was carefully coordinated around daily operations, allowing brewing to continue with no interruption.

"They were very respectful and professional working in a live production environment," said Hixon. "Really, there was no lost production time."

A model for other facilities

Every brewery depends on reliable electricity and large volumes of hot water. The mCHP system addresses both needs simultaneously by generating electricity while recovering heat that would otherwise be wasted.

For breweries and other businesses with continuous thermal and electrical demand, mCHP can be a practical way to improve efficiency, reduce operating costs, and make better use of the energy they already consume.


Explore your facility upgrade path

See how mCHP is helping breweries, food processors, and other industries improve efficiency, lower operating costs, and strengthen operational reliability by making better use of energy they already consume.

Interested in learning how mCHP can work for your building?

Contact innovative-solutions@peoplesgasdelivery.com to discuss your options.





Technical Specifications

MODEL XRG 25	2 UNITS
KW OUTPUT	48
FLA @ 100%	82
Recommended Natural Gas Pressure Range	8 - 10" w.c.
Combustion Air Net Free Area	48 sq. in.
INPUT MBH @100%	524
OUTPUT MBH @100%	328
MANIFOLD A SIZE - MINIMUM	2"
MANIFOLD B SIZE - MINIMUM	2"
STORAGE CONTROL - PANELS / SENSORS	4 / 16
TANK RELIEF VALVE SIZE / PRESS	3/4" / 80 PSI

Bill of Material

ITEM	DESCRIPTION
P1	PUMP B&G PL-46 C.I./S.S. 1/8 HP 1.5" Flanges 115/80/1 *
P2	
P3	
ST1 & 2	NILES TANK - Model S-36-102 415 GALLON BUFFER TANK. SC sensors to be field installed. To be field insulated
HX1	HEXONIC - Safety Plate Double Walled Braze Plate Heat Exchanger JB478P-60H-1'-UM approx 336 MBH
ET-1	AMTROL SX-80V OR EQUAL
PRV-1	B&G MODEL B-38 OR EQUAL SET TO 12 PSI
FM 250	FLOW MASTER MODEL FM 250 208/1/80"
*	Provide ground per NEC and local electric code

SCOPE:

The goal of this project is to reduce electrical consumption and reduce the electrical demand charge for the facility. All the heat provided by the CHP units will reduce the heat generated by the existing steam boiler.

19 WEST COLLEGE DRIVE
ARLINGTON HEIGHTS, IL 60004
(847) 253-1040

BOILERSOURCE.COM

DRAWN BY
AGR

CHECKED BY

SCALE
NONE

PROJECT

DRAWING TITLE

SCALE

HALF ACRE BEER COMPANY
EC POWER 2 - XRG 25 SYSTEMS,
2 - BUFFER TANKS, HEATING, & DHW HX

REVISION
12

DATE

10/30/25

SHEET

Enginuity CHP

- 100 and 200kW CHP systems available
- Continuous on-site power and hot water
- Usable heat for facility needs
- Higher total efficiency
- Energy that works every day
- Maintain continuous operations
- Reduce exposure to grid disruptions
- Make better use of the energy they already consume



**Meaning more value from every unit of energy
vs. ~55% efficiency from even the best grid power plants**

E|200 Spec Summary



Energy Efficiency
PROGRAM

- Powered by: natural gas
- EPA and UL certified
- 180kW continuous electric output (peak at 200kW)
- Approx. 1.1M BTUs output
- 58 gallons per minute H₂O at 203° F



ENGINE POWER SYSTEMS			
STATIONARY ENGINE GENERATOR ASSEMBLY			
MANUFACTURING DATE	Feb. 2025		
GENSET MODEL	KGP-200NE	GENSET S/NO.	KGP-2002502-02
ENGINE MODEL	C6AF	ENGINE S/NO.	C6AFR1399195
GENERATOR MODEL	LSA 463S4	GENERATOR S/NO.	860115 001
DATA			
POWER	250kVA / 200kW	INSULATION CLASS	Class H
VOLTAGE	480 / 277V	AMBIENT TEMP.	104°F/40°C
FREQUENCY	60Hz	SYNCHRONOUS IMPEDANCE(Zd)	2.98Ω
PHASE	3-Phase, Yye connection	TRANSIENT IMPEDANCE(Zd')	0.93Ω
POWER FACTOR	0.8	SUBTRANSIENT IMPEDANCE(Zd'')	0.93Ω
SPEED	1800rpm	ZERO SEQUENCE IMPEDANCE(Zd0)	0.92Ω
OVERCURRENT AND OVERLOAD PROTECTION Provided			
THE GENERATOR MUST BE GROUNDED AND INSTALLED IN COMPLIANCE WITH LOCAL ELECTRICAL CODES.			



E|200 and E|100 Spec Deep Dive



Energy Efficiency
PROGRAM



200KW SPECIFICATIONS

ENGINLUITY
POWER SYSTEMS

Electric Power Output	Peak	200kW
	Continuous	180kW
	Standby	150kW
	Voltage / Frequency	480VAC / 60Hz
	Output Wiring	3 phase / 4 wire
System Efficiency	Electric Generation Efficiency	31.3%
	Heat Recovery Efficiency	53.7%
	Overall Efficiency	85.0%
Engine	Manufacturer	Hyundai
	No. of Cylinder	6
	Aspiration	Turbo Charged Intercooler
Fuel	Fuel Types	Natural Gas, Propane*
	Fuel Pressure - Minimum	5 kPa (20 inch w.c.)
	Fuel Pressure - Maximum	40 kPa (161 inch w.c.)
	Fuel Consumption (flow)	57.5 m ³ /hr (33.8 ft ³ /min)
	Fuel Consumption Rate**	1,962,700 BTU/hr
Sound Level	Fuel Connection Port Size	NPT 1-1/2" (40A)
	Measured at 9.84ft (3m)	85 dBA
Dimension	Length	3,200 mm (126 in)
	Width	1,830 mm (76 in)
	Height	2,158 mm (85 in)
	Height (with cooling fans)	2,486 mm (98 in)
	Weight (dy, no fluids added)	3,200 kg (7,055 lb.)
Thermal Output	Peak	336 kW (1,146,000 BTU/hr)
	Continuous	309 kW (1,054,000 BTU/hr)
	Standby	263 kW (897,000 BTU/hr)
Water	Temp difference supply / return (ΔT)	20 °C (36 °F)
	Output Water Temp - Max	95 °C (203 °F)
	Water Flow - Max rated	221 LPM (58.4 GPM)
	Water Connection Port Size	2" (50A)

Notes:
*all performance specs are based on natural gas, for detailed performance on propane contact EPS
**based on LHV of 34,129 BTU / m³

100KW SPECIFICATIONS

ENGINLUITY
POWER SYSTEMS

Electric Power Output	Peak	110kW
	Continuous	100kW
	Standby	100kW
	Voltage / Frequency	480VAC / 60Hz
	Output Wiring	3 phase / 4 wire
System Efficiency	Electric Generation Efficiency	30.8%
	Heat Recovery Efficiency	54.2%
	Overall Efficiency	85.0%
Engine	Manufacturer	Hyundai
	No. of Cylinder	6
	Aspiration	Natural Aspiration
Fuel	Fuel Types	Natural Gas, Propane*
	Fuel Pressure - Minimum	5 kPa (20 inch w.c.)
	Fuel Pressure - Maximum	40 kPa (161 inch w.c.)
	Fuel Consumption (flow)	28.5 m ³ /hr (16.8 ft ³ /min)
	Fuel Consumption Rate**	972,700 BTU/hr
Sound Level	Fuel Connection Port Size	NPT 1-1/2" (40A)
	Measured at 9.84ft (3m)	85 dBA
Dimension	Length	2,980 mm (117 in)
	Width	1,630 mm (64 in)
	Height	2,256 mm (89 in)
	Height (with cooling fans)	2,486 mm
	Weight (dy, no fluids added)	3,000 kg (6,613 lb.)
Thermal Output	Peak	194 kW (662,000 BTU/hr)
	Continuous	183 kW (624,000 BTU/hr)
	Standby	183 kW (624,000 BTU/hr)
Water	Temp difference supply / return (ΔT)	20 °C (36 °F)
	Output Water Temp - Max	95 °C (203 °F)
	Water Flow - Max rated	139 LPM (36.7 GPM)
	Water Connection Port Size	2" (50A)

Notes:
*all performance specs are based on natural gas, for detailed performance on propane contact EPS
**based on LHV of 34,129 BTU / m³

Why Are We Here Today?



Energy Efficiency
PROGRAM

- Identify the Issues
- Review the Technologies
- Meet the Manufacturers and Products
- **Target Markets and Applications**
- Making it Easy

Applications



Energy Efficiency
PROGRAM



Indoor Agriculture



Distilleries



Manufacturing



Hotels



Pharmaceutical Lab



Sports Club



Multi-Family



Hospitals



Industrial



Food Processing



Nursing Homes



Municipal

Why Are We Here Today?



Energy Efficiency
PROGRAM

- Identify the Issues
- Review the Technologies
- Meet the Manufacturers and Products
- Target Markets and Applications
- **Making it Easy**

What Makes Us Special



Energy Efficiency
PROGRAM

- Field and internal support teams.
 - System evaluation, design, troubleshooting, training, startup, etc.
- Bridge between our system manufacturers and the industries we serve.
 - Experience and responsiveness during the design phase and installation.
 - We will work with MFES assessors and Trade Ally Contractors to make the process easy.
- Work with manufacturers to ensure their products continuously improve.
- WBE/DBE





Tony Ranallo

COO/ Principal

(847) 770-0788 cell

tony@boilersource.com

Follow me on LinkedIn

[linkedin.com/in/tony-ranallo-4389131b](https://www.linkedin.com/in/tony-ranallo-4389131b)



Energy Efficiency
PROGRAM



BOILERSOURCE

Going Beyond the Boilerplate

*We are a nationally certified Women-owned Business Enterprise (WBE)
Going Strong for Over 50 Years!*



*Let us tell you about
our TLC360° promise!*

Follow BOILERSOURCE on LinkedIn

THANK YOU